



No. MCC/341/2025-SUP-CL-II/

14-02-2026

Department of Engineering & Maintenance

**QUOTATION NOTICE**

Sealed quotations are invited from experienced and eligible contractors/agencies for the **Construction of differently-abled toilet in IP Block** (modification of an existing toilet) at Malabar Cancer Centre (PGIOSR), as per the standard specifications and details given below.

**TERMS AND CONDITIONS**

1. Name of work: **Construction of differently-abled toilet in IP Block**
2. Last date & time for submission of quotation: Upto 3.00 PM on 23-02-2026
3. The contractor shall inspect the site before submitting the quotation.
4. The work shall be carried out as per standard specifications and as directed by the Engineer-in-Charge.
5. The quotation shall be unconditional. Conditional quotations are liable to be rejected.
6. The quoted rate shall be **excluding GST and** inclusive of all other taxes, duties, labour charges, carriage, tools & plants, contractor's profit and overheads.
7. Valid GST registration certificate must be attached.
8. No extra claim will be entertained under any circumstances.
9. The work shall be completed within 45 days from the date of issue of work order.
10. The Director, Malabar Cancer Centre, reserves the right to accept or reject any or all quotations without assigning any reason.
11. The work shall be completed within the time stipulated by the Engineer-in-Charge.
12. Payment will be made after satisfactory completion of the work as per the actual measurements at site and submission of the bill. All safety and security rules of Malabar Cancer Centre (PGIOSR) shall be strictly followed.
13. Any damage caused to MCC (PGIOSR) property during execution shall be made good by the contractor at his/her own cost.
14. Any defects noticed during the defect liability period shall be rectified by the contractor at their own cost.
15. The quotation should be sent to The Director, Malabar Cancer Centre (PGIOSR), Moozhikkara (P.O.), Kannur- 670103, Kerala, India.
16. BOQ for the above work is attached herewith, Rate for each work should be quoted by the Contractor.
17. The quotation should be submitted in the prescribed format.

The sealed quotation should be submitted in the sender/quotation box kept at the Purchase Division, MCC (PGIOSR) Quotations in other formats will not be accepted. The last date for submission of quotations is 23-02-2026 at 3.00 p.m. The quotations will be opened at 3.30 PM on the same day. Information regarding the quotations can be obtained from MCC Engineering & Maintenance dept. Tel: 0490-2399226.

**Sd/-**  
**DIRECTOR**

**Copy to:** 1) Notice Board in MCC (PGIOSR) 2) Official Website

**MALABAR CANCER CENTRE (POST GRADUATE INSTITUTE OF ONCOLOGY SCINECES AND RESEARCH)**

BILL OF QUANTITIES						
Name of work: Construction of differently-abled toilet in IP Block						
SI No	Specification	Quantity	Type	Rate		Amount
				in figure	words	
<b>1</b>	<b>Modification of existing toilet to Disabled Toilet</b>					
1.001	14.4.1 Making the opening in brick masonry including dismantling in floor or walls for door/ window/ clerestory window	4.340	Sqm			
1.002	15.23.2 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead for thickness of tiles above 25 mm and up to 40 mm	7.940	Sqm			
1.003	13.1.1 12 mm cement plaster of mix:1:4 (1 cement: 4 fine sand)	2.152	Sqm			
1.004	9.121 Providing and fixing Glass Fiber Reinforced Plastic (FRP) Door Frames of cross- section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness. The laminated shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2 mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame.	5.280	Metre			

**MALABAR CANCER CENTRE (POST GRADUATE INSTITUTE OF ONCOLOGY SCINECES AND RESEARCH)**

SI No	Specification	Quantity	Type	Rate		Amount
				in figure	words	
1.005	9.122.1 Providing and fixing to existing door frames.30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS : 14856, including fixing to frames.	1.845	Sqm			
1.006	9.165.1 Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete.125 mm	2.000	No			
1.007	9.97.3 Providing and fixing aluminium tower bolts, ISI marked, anodised(anodic coating not less than grade AC 10 as per : 1868), transparent or dyed to required colour or shade, with necessary screws complete:200x10 mm	6.000	No			
1.008	15.13.1 Taking out doors, windows and clerestory window shutters (steel or wood ) including stacking within 50 metres lead: Of area 3 sq. metres and below	2.000	Each			

**MALABAR CANCER CENTRE (POST GRADUATE INSTITUTE OF ONCOLOGY SCINECES AND RESEARCH)**

SI No	Specification	Quantity	Type	Rate		Amount
				in figure	words	
1.009	21.1.1.2 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminnium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	8.338	Kg			
1.010	21.1.2.2 For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/ neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	11.261	Kg			
1.011	11.47.2 Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS : 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm	1.830	Sqm			

**MALABAR CANCER CENTRE (POST GRADUATE INSTITUTE OF ONCOLOGY SCINECES AND RESEARCH)**

SI No	Specification	Quantity	Type	Rate		Amount
				in figure	words	
1.012	11.48.2 Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg). including filling /grouting and finishing complete as per direction of Engineer-in-charge.Size of Tile 600x600 mm	1.830	Sqm			
1.013	10.28 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	8.518	Kg			
1.014	13.83.2 Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile including applying additional coats wherever required to achieve even shade and colour.Two coats	49.137	Sqm			
1.015	OD274534/2025-2026 Providing and fixing 4mm thick ACP sheet, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in- Charge.	1.655	Sqm			
				<b>Total Amount</b>		
				<b>Grand Total</b>		
<b>(Rupees ..... Only</b>						